

## Summary of Preliminary Assessment on Structural, Fire and Electrical Safety

---

Name of the Factory : ABG Sweaters Limited  
Address of the Factory : Teknagpara, Chandana Chowrasta, Gazipur Chowsasta, Gazipur  
Present Status of the Factory : Under Operation  
Structural Assessment Conducted by : BUET  
Date of Structural Inspection : 14<sup>th</sup> January 2014  
Fire & Electrical Assessment Conducted by : BUET  
Date of Fire & Electrical Inspection : 12<sup>th</sup> February 2014

### **BASIC INFORMATION:**

The factory building is a six storied RC frame building. The following information was noted:

- i. Building Usage Type : Garment factory building
- ii. Structural System : Steel gable frame structure
- iii. Floor System : Steel deck
- iv. Floor Area : Approximately 8000 sft (744 sq. m) per floor (Grid spacing mostly 20 ft × 20 ft)
- v. No. of Stories : two story
- vi. Construction Year : 2007-2009
- vii. Foundation Type : Isolated column footing (as per drawing).
- viii. Design Drawings : Structural and Architectural Drawing is available.
- ix. Soil Boring Report : Available
- x. Construction Materials : Mild Steel
- xi. Generator : Out Side of Building.

### **RECOMMENDATIONS FOR CORRECTIVE ACTION:**

The recommendations of corrective action for both Structural and Fire & Electrical Safety comprises in Short Term, Mid Term and Long Term basis.

The recommendations for **Structural Safety** corrective action are:

Short Term (Immediate) : None  
Mid Term (6-weeks) : None  
Long Term (6-months) : None

The recommendations for **Fire & Electrical Safety** corrective action are:

**(A): Recommendations for Fire Safety corrective actions:**

Immediate  <i>(the factory should not continue to be occupied until these non-conformities have been rectified):</i>	N/A
--	-----

## Summary of Preliminary Assessment on Structural, Fire and Electrical Safety

<p>Short Term</p> <p><i>(Actions that must be incorporated into a Fire Safety Management Plan immediately (a week) and should be a regular activity)</i></p>	<p>Remove all temporary obstructions from all escape routes, aisles and passageways.</p> <p>Remove all combustible materials from substation/generator room.</p> <p>Ensure adequate numbers of fire drills.</p> <p>Ensure easy access to portable extinguishers and monitor and maintain the same at required interval as per guidelines.</p> <p>Provide proper directional sign and exit sign in Bangla and English as per guidelines.</p>
<p>Mid Term</p> <p><i>(The remedial works indicated must be carried out within a period of 6 weeks)</i></p>	<p>Produce proper drawing and plans to create horizontal and vertical fire-rated separation for stairways of appropriate specifications, grills, storage and assembly areas, offices, work areas. Also design to ensure proper separation of high risk areas (e.g., generator, boiler, transformer and substation rooms) as per guidelines.</p> <p>Remove all sliding doors. Produce design drawings to demonstrate how stairways are to be made of adequate dimensions and appropriate specifications and to be converted into fire-rated enclosures equipped with fire-rated side swinging doors of required dimensions opening in the direction of travel at each floor.</p> <p>Produce design to install standard standpipe, hose and fire pump system.</p> <p>Provide design to install proper detection and alarm system.</p> <p>Install command station as per guidelines.</p>
<p>Long Term</p> <p><i>(The remedial works indicated must be carried out within a period of 6 months)</i></p>	<p>Install horizontal and vertical fire-rated separation for stairways of appropriate specifications, grills, storage and assembly areas, offices, work areas.</p> <p>Ensure proper fire separation of high risk areas (e.g., generator, boiler, transformer and substation rooms) as per approved design.</p> <p>Install fire rated enclosure and doors of appropriate dimensions at exit to the stairs to prevent smoke and fire propagation as per approved design.</p> <p>Install standard standpipe, hose and fire pump system.</p> <p>Install proper detection and alarm system.</p> <p>Provide fire rated enclosure, install self closing fire rated door as per guidelines.</p>

### **(B): Recommendations for Electrical Safety corrective actions:**

<p>Immediate</p> <p><i>(the factory should not continue to be</i></p>	<p>N/A</p>
---	------------

## Summary of Preliminary Assessment on Structural, Fire and Electrical Safety

<p><i>occupied until these non-conformities have been rectified):</i></p>	
<p>Short Term</p> <p><i>(Actions that must be incorporated into a Fire Safety Management Plan immediately (a week) and should be a regular activity</i></p>	<p>Provide instructions for first aid and artificial respiration from exposure to electrical shock.</p> <p>Provide cover on the cable trench and rubber mat in front of the panel.</p> <p>Ensure well-dressed cabling with lugs and remove loose cabling.</p> <p>Ensure earthing of panel body &amp; door with fitted condition.</p> <p>Provide distribution board as per guideline and put identification mark on distribution panel.</p> <p>Remove broken/loose MCB/MCCB box/socket.</p>
<p>Mid Term</p> <p><i>(The remedial works indicated must be carried out within a period of 6 weeks)</i></p>	<p>Provide separate service ducts for electrical cables.</p> <p>Provide new Emergency Lighting system.</p> <p>Provide appropriate Lightning Protection System as per guidelines.</p>
<p>Long Term</p> <p><i>(The remedial works indicated must be carried out within a period of 6 months)</i></p>	<p>N/A</p>